



SHED REFURBISHMENT

48 SIPPY CREEK ROAD, TANAWHA 4566

SUNSHINE COAST REGIONAL COUNCIL



RPD

LOT 427

SP 237585

SITE CLASSIFICATION

THIS SITE HAS BEEN CLASSIFIED IN ACCORDANCE WITH AS2870-2011 AS CLASS 'H' BY CSI SOIL TESTING REPORT NUMBER 11137 ON THE 21/03/2017

SCHEDULE OF DRAWINGS

DWG	DESCRIPTION
1417 03 H 100	SITE PLAN & DRAWING SCHEDULE
1417 03 H 110	GENERAL NOTES
1417 03 H 200	HYDRAULIC SITE PLAN
1417 03 H 300	SANITARY DRAINAGE & WATER RETICULATION FLOOR PLAN



SITE PLAN
NOT TO SCALE



UNITY WATER MAPPING



SCRC MAPPING

PLAN DETAILS:		PLAN AMENDMENTS:				
Designed:	RM	Rev	Date	Comment	Altered	Checked
Drawn:	RM	A	17/12/21	FOR APPROVAL	RM	JT
Checked:	BAT					
Datum:	AHD					
Date:	DEC 2021					

PROPOSED SHED REFURBISHMENT

48 SIPPY CREEK RD, TANAWAH

SUNSHINE COAST REGIONAL COUNCIL

© This plan is Copyright. Other than for the purposes of and subject to the conditions prescribed under the Copyright Act, no part of it may in any form or by any means be reproduced, stored in a retrieval system or transmitted without the prior written permission of Contour Consulting Engineers. The plan shall not be used for construction without prior written approval.

PLAN TITLE:	
SITE PLAN AND DRAWING SCHEDULE	
PLAN No: 1417 03 H 100	REVISION: A




CONTOUR

A.B.N. 62 117 061 659
PO Box 474, Buddina 4575, Qld
6 Innovation Parkway, Kawana Waters 4575, Qld
Ph. (07) 5493 9777 Fax (07) 5493 6888
Website: www.ContourCE.com.au




127
Quality Assured
International 3rd Party Accredited


TENDER




SANITARY DRAINAGE SCHEMATIC
NOT TO SCALE




TYPICAL PIPE THROUGH FOOTING DETAIL - SECTION
SCALE = 1:20




TYPICAL UNDER WAFFLE SLAB PIPE DETAIL
SCALE = 1:20



TYPICAL PUMP OUT DETAIL
NOT TO SCALE




TYPICAL O.R.G DETAIL
NOT TO SCALE




TYPICAL I.O.S DETAIL
NOT TO SCALE

MINIMUM REQUIREMENTS FOR SEWER ARTICULATION			
SITE CLASS	DESIGN Ys MOVEMENT (mm)	SEWER EXIT POINTS & ORG	
		SWIVEL	EXPANDER
M	Ys<40	0	0
H1	40<Ys ≤ 60	1	1
H2	60<Ys ≤ 75	2	1
E	Ys >75	2	1

NOTE:
EXPANDER REQUIRED ON ALL RISERS FOR (CLASS E, Ys >75mm OR EQUIVALENT SITES



TYPICAL PIPE INSTALLATION NEAR FOOTING DETAIL
NOT TO SCALE



PROHIBITED ZONES FOR CONNECTIONS IN STACKS AND ELEVATED DRAINAGE
NOT TO SCALE

EQUIVALENT PIPE SIZING

PIPE SIZE 'ID'	COPPER, PVC and DICL Pipes		POLYETHYLENE Pipes	
	MATERIAL	ID mm	PE OD	ID PN12.5
15	COPPER	13	-	-
18	COPPER	16	-	-
20	COPPER	19	25	21
25	COPPER	25	32	27
32	COPPER	32	40	34
40	COPPER	38	50	42
50	COPPER	51	63	53
65	COPPER	64	90	76
80	COPPER	76	110	94
100	PVC-M - PN12	110	125	106
	DICL - PN35	102		

APPROXIMATE SIZES ONLY TO BE CONFIRMED WITH MANUFACTURER

SANITARY DRAINAGE

1. Pipes under footings shall have a minimum clearance of 75mm from top of pipe to underside of footing.
2. Pipes passing through footings shall be fully lagged (20mm thickness for class 'M' & 40mm thickness for class 'H' soils) and sleeved.
3. Grades for plumbing pipes refer AS3500.2.2, generally use:
minimum grade of 1:40 for 40mm, 50mm & 65mm dia pipes
minimum grade of 1:60 for 80mm & 100mm dia pipes
4. All baths and showers to floor waste to be max 1200mm untrapped or max 2500mm trapped.
5. All unvented branch drains to be installed in accordance with AS3500.2.2
6. All works to be in accordance with The Plumbing & Drainage Act 2018 and AS3500 National Plumbing & Drainage Code
7. Work to be to the approval of the Local Council.
8. All pipe penetrations of slabs and fire rated walls are to incorporate approved fire collars.
9. All vents to terminate in accordance with AS/NZS3500.2.2
10. Soil, waste and vent pipes shall be UPVC unless otherwise notes.
11. Trade waste pipes shall be HDPE.
12. Provide sealed expansion coupling joints to all risers and slab penetrations in moderately and highly reactive clay sites.

WATER RETICULATION


1. All water pipework shall comply with The Plumbing & Drainage Act 2018 and relevant Australian Standards.
3. Provide all necessary allowances for thermal movement of pipes
4. Minimum pipe size for connection to:-
- 15mm dia. <3m length 1 fixture
- 18mm dia. <6m length 1 fixture
- 20mm dia. 15 fixtures
5. Pipe dia shown on plan indicate the min. internal dia of the pipes.
7. Provide isolating valves to all testable valves in an accessible position.
8. Hot water units are to be installed to AS3500 and manufactures specifications.
9. All hot water pipework is to be lagged.
10. All pipework passing through walls and floors is to be fully lagged and sleeved.
11. All hose cocks to be fitted with vacuum breakers
12. The following materials shall be employed in the domestic hot, cold and tempered water reticulation system.
 - Copper type B - external above ground
 - HDPE PN12.5 - external below ground
 - Cross linked high denisty polyethylene - internal hot and cold
 - Chrome plate - internal exposed

FIXTURE LEGEND


BN	- BASIN, 40mm WASTE AND TRAP
BB	- BABY BATH, 40mm WASTE AND TRAP
BM	- BAIN MARIE
BTH	- BATH, 40mm WASTE AND TRAP
BFW	- BUCKET FLOOR WASTE
CS	- CLEANERS SINK
DCV	- DOUBLE CHECK VALVE
DF	- DRINKING FOUNTAIN
ED	- ELEVATED DRAINAGE
FHR	- FIRE HOSE AND REEL
FL	- FLOOR LEVEL
FW	- FLOOR WASTE GULLY
GW	- GLASS WASHER
HC	- HOSE COCK
HWS	- HOT WATER SYSTEM
IC	- INSPECTION CHAMBER
IL	- INVERT LEVEL
IO	- INSPECTION OPENING
IOS	- INSPECTION OPENING TO SURFACE
MH	- MANHOLE
ORG	- OVERFLOW RELIEF GULLY, 100mm TRAP
RL	- REDUCED LEVEL
SFW	- SEALED FLOOR WASTE GULLY
SHR	- SHOWER, 40mm WASTE
SNK	- SINK, 50mm WASTE AND TRAP
SL	- SLUICE SINK
TUB	- LAUNDRY TROUGH, 50mm WASTE AND TRAP
TD	- COPPER TUDISH
TG	- TEST GATE
TV	- TEMPERING VALVE
UR	- URINAL
WC	- WATER CLOSET, 100mm INTERGRAL TRAP
WM	- WASHING MACHINE, TO TUB BY-PASS.

PLAN DETAILS:				
Designed:	RM			
Drawn:	RM			
Checked:	BAT			
Datum:	AHD			
Date:	DEC 2021			
RPEQ 6068				


PLAN AMENDMENTS:				
Rev	Date	Comment	Altered	Checked
A	17/12/21	FOR APPROVAL	RM	JT




SANITARY PIPE TRENCH
NOT TO SCALE



**TYPICAL WATER RETICULATION AND
SANITARY DRAINAGE SHARED TRENCH**
NOT TO SCALE




WATER PIPE TRENCH
NOT TO SCALE



**ROOF WATER DRAINAGE
AND REUSE SCHEMATIC**
NOT TO SCALE

MINIMUM PIT SIZE vs DEPTH

DEPTH	SIZE
<600	450x450
600-900	600x600
900-1200	600x900
>1200	900x900



TYPICAL S/W PIT
NOT TO SCALE

STORMWATER DRAINAGE

GENERAL

Drains:

Provide stormwater drains to connect downpipes, surface drains, subsoil drains and drainage pits to the outlet point or point of connection.

Downpipe connections:

Turn up drain lines with bends to meet the downpipe, finishing 50 mm (nominal) above finished ground or pavement level. Provide sealed expansion couplings between downpipes and drains.

Pipe Materials:

Stormwater pipe to be F.R.C. or U.P.V.C. class SH in accordance with AS3500.3 Connection to kerb to be galvanised RHS in accordance with AS1074 with minimum coating mass of 500g/sqr.m

Identification:

Lay a detectable strip or plastic tape in the trench after pipelaying, testing and initial backfilling.

PIPE UNDERLAY

General:

Bed piping on a continuous underlay of bedding material, at least 75 mm thick after compaction. Grade the underlay evenly to the gradient of the pipeline.

Chases:

If necessary, form chases to prevent projections such as sockets and flanges from bearing on the trench bottom or underlay.

PIPE SURROUNDS

General:

Place the material in the pipe surround in layers 200 mm loose thickness, and compact without damaging or displacing the piping. Anchor blocks if necessary, provide anchor blocks which restrain lateral and axial movement of the pipelines at junctions and changes of grade or direction.

ENCASEMENT

General:

If necessary, encase the pipeline in concrete at least 150 mm above and below the pipe, and 150 mm each side or the width of the trench, whichever is the greater. Use Grade N20 concrete to AS 1379.

SUBSOIL DRAINS

General:

Provide subsoil drains to intercept groundwater seepage and prevent water build-up behind walls and under floors and pavements. Connect subsoil drains to surface drains or to the stormwater drainage system as applicable.

Pipe Size & Class:

100mm minimum diameter in accordance with AS2439.1

Pipe depth:

Provide the following minimum clear depths, measured to the crown of the pipe, where the pipe passes below the following elements:

- 100 mm below formation level of the pavement, kerb or channel.
- 100 mm below the average gradient of the bottom of footings.
- 450 mm below the finished surface of unpaved ground.

Jointing:

At junctions of subsoil pipes provide tees, couplings or adaptors to AS 2439.1.

Trench width:

Minimum 450 mm.

Pipe underlay:

Grade the trench floor evenly to the gradient of the pipeline. If the trench floor is rock, correct any irregularities with compacted bedding material. Bed piping on a continuous underlay of bedding material, at least 75 mm thick after compaction. Lay the pipe with one line of perforations at the bottom.

Chases:

If necessary, form chases to prevent projections such as sockets and flanges from bearing on the trench bottom or underlay.

Pipe surrounds:

Place the material in the pipe surround in layers 200 mm loose thickness, and compact without damaging or displacing the piping.

Depth of overlay:

- To the underside of the bases of overlying structures such as pavements, slabs and channels.
- To within 150 mm of the finished surface of unpaved or landscaped areas.

Filter fabric:

Provide polymeric fabric formed from plastic yarn composed of at least 85 by weight propylene, ethylene, amide or vinylidenechloride, and containing stabilisers or inhibitors which provide resistance to deterioration due to ultraviolet light.

Marking:

To AS 3705. Protection: Provide heavy duty protective covering. Store clear of the ground and out of direct sunlight. During installation do not expose the filter fabric to sunlight for more than 14 days.

Filter socks:

Provide polyester permeable socks capable of retaining particles of 0.25 mm size. Securely fit or join the sock at each joint.

PITS

General:

Finish to exposed surfaces. Co-ordinate finishes with landscape Architect, provide a smooth, seamless finish, using steel trowelled render or concrete cast in steel forms.

Corners:

Cove or splay internal corners. Metal access covers and grates Standard: To AS 3996.

Cover levels:

Top of cover or grate, including frame:

- In paved areas: Flush with the paving surface.
- In landscaped areas: 25 mm above finished surface.



CONTOUR

A.B.N. 62 117 061 659
PO Box 474, Buddina 4575, Qld
6 Innovation Parkway, Kawana Waters 4575, Qld
Ph. (07) 5493 9777 Fax (07) 5493 6888
Website: www.ContourCE.com.au



PLAN DETAILS:

Designed: **RM**
Drawn: **RM**
Checked: **BAT**
Datum: **AHD**
Date: **DEC 2021**

RPEQ 6068

PLAN AMENDMENTS:

Rev	Date	Comment	Altered	Checked
A	17/12/21	FOR APPROVAL	RM	JT

PROPOSED SHED REFURBISHMENT 48 SIPPY CREEK RD, TANAWAH SUNSHINE COAST REGIONAL COUNCIL

© This plan is Copyright. Other than for the purposes of and subject to the conditions prescribed under the Copyright Act, no part of it may in any form or by any means be reproduced, stored in a retrieval system or transmitted without the prior written permission of Contour Consulting Engineers. The plan shall not be used for construction without prior written approval.

PLAN TITLE:

GENERAL NOTES

PLAN No: **1417 03 H 111**

REVISION: **A**


TENDER



LINE TYPE LEGEND
SITE HYDRAULICS

---	PROPOSED WATER SERVICE
---	PROPOSED SANITARY DRAINAGE
---	PROPOSED STORMWATER DRAINAGE


CONTRACTOR TO CONSULT WITH SCRC PRIOR TO ANY EXCAVATION WORKS TO CONFIRM ALIGNMENT ADJACENT TO EXISTING TREES. GENERALLY ALL EXCAVATIONS TO BE UNDERTAKEN OUTSIDE OF EXISTING TREE DROP LINE



HYDRAULIC SITE PLAN
SCALE 1:200

GENERAL NOTES

1. REFER SHEETS 110 & 111 FOR GENERAL NOTES, DETAILS, SCHEMATICS AND FIXTURE LEGEND.
2. PROVIDE EXPANSION AND SWIVEL JOINTS TO ALL PIPE WORK UNDER BUILDING TO SUIT SITE SOIL CLASSIFICATION.
3. ALL FIXTURES, APPLIANCES AND APPARATUS CONNECTED TO THE PLUMBING SYSTEM ARE TO HAVE WATERMARK CERTIFICATION OR COMPLY WITH THE PLUMBING CODE OF AUSTRALIA PART A2.
4. ALL SANITARY DRAINAGE & PLUMBING IS TO BE DESIGNED, INSTALLED, TESTED AND LABELED IN ACCORDANCE WITH AS/NZS 3500.2.2018 AND THE PLUMBING CODE OF AUSTRALIA REQUIREMENTS.
5. ALL WATER SUPPLY IS TO BE DESIGNED, INSTALLED, TESTED AND LABELED IN ACCORDANCE WITH AS/NZS 3500.1.2018 AND THE PLUMBING CODE OF AUSTRALIA REQUIREMENTS.



CONTOUR

A.B.N. 62 117 061 659
PO Box 474, Buddina 4575, Qld
6 Innovation Parkway, Kawana Waters 4575, Qld
Ph. (07) 5493 9777 Fax (07) 5493 6888
Website: www.ContourCE.com.au



PLAN DETAILS:

Designed: **RM**
Drawn: **RM**
Checked: **BAT**
Datum: **AHD**
Date: **DEC 2021**

RPEQ 6068

PLAN AMENDMENTS:

Rev	Date	Comment	Altered	Checked
A	17/12/21	FOR APPROVAL	RM	JT

**PROPOSED SHED REFURBISHMENT
48 SIPPY CREEK RD, TANAWAH
SUNSHINE COAST REGIONAL COUNCIL**

© This plan is Copyright. Other than for the purposes of and subject to the conditions prescribed under the Copyright Act, no part of it may in any form or by any means be reproduced, stored in a retrieval system or transmitted without the prior written permission of Contour Consulting Engineers. The plan shall not be used for construction without prior written approval.


PLAN TITLE:

HYDRAULIC SITE PLAN

PLAN No: **1417 03 H 200**


TENDER

REVISION: **A**



SANITARY DRAINAGE FLOOR PLAN

SCALE 1:100



WATER RETICULATION FLOOR PLAN

SCALE 1:100

WATER NOTES

1. REFER SHEETS 110 & 111 FOR GENERAL NOTES, DETAILS, SCHEMATICS AND FIXTURE LEGEND.
2. ALL FIXTURES, APPLIANCES AND APPARATUS CONNECTED TO THE PLUMBING SYSTEM ARE TO HAVE WATERMARK CERTIFICATION OR COMPLY WITH THE PLUMBING CODE OF AUSTRALIA PART A2.
4. PRESSURE REDUCTION VALVE TO BE INSTALLED TO ENSURE MAXIMUM STATIC PRESSURE AT ANY OUTLET DOES NOT EXCEED 500kPa IN ACCORDANCE WITH AS/NZS3500.1:2018 CLAUSE 3.3.4
5. ALL WATER SUPPLY IS TO BE DESIGNED, INSTALLED, TESTED AND LABELED IN ACCORDANCE WITH AS/NZS 3500.1:2018 AND THE PLUMBING CODE OF AUSTRALIA REQUIREMENTS.
6. HOT WATER SUPPLY TEMPERATURE TO PERSONAL HYGIENE FIXTURES TO COMPLY WITH AS/NZS3500.4:2018 CLAUSE 1.9

LINE TYPE LEGEND WATER RETICULATION

- PROPOSED WATER COLD
- H-H- PROPOSED WATER HOT
- T-T- PROPOSED WATER TEMPER

SANITARY NOTES

1. REFER SHEETS 110 & 111 FOR GENERAL NOTES, DETAILS, SCHEMATICS AND FIXTURE LEGEND.
2. PROVIDE EXPANSION AND SWIVEL JOINTS TO ALL PIPE WORK UNDER BUILDING TO SUIT SITE SOIL CLASSIFICATION.
3. ALL FIXTURES, APPLIANCES AND APPARATUS CONNECTED TO THE PLUMBING SYSTEM ARE TO HAVE WATERMARK CERTIFICATION OR COMPLY WITH THE PLUMBING CODE OF AUSTRALIA PART A2.
4. ALL SANITARY DRAINAGE & PLUMBING IS TO BE DESIGNED, INSTALLED, TESTED AND LABELED IN ACCORDANCE WITH AS/NZS 3500.2:2018 AND THE PLUMBING CODE OF AUSTRALIA REQUIREMENTS.

PIPE ARTICULATION

PLUMBING CONTRACTOR MUST INSTALL SLIP JOINTS BETWEEN DOWN PIPES AND IN GROUND DRAINAGE. PROVIDE PLASTEC SWIVEL JOINT OR EQUIVALENT AND SLIP JOINTS BETWEEN SLAB/FOOTING PENETRATIONS AND JUNCTIONS AND IN GROUND TANKS AND WELLS.

PIPE ARTICULATION LEGEND


- ⊗ TYPICALLY DENOTES SWIVEL/SLIP COMBINATION JOINTS REFER TYPICAL DETAILS
- TYPICALLY INSTALL SLIP JOINTS WHERE SHOWN, REFER TYPICAL DETAILS

LINE TYPE LEGEND SANITARY DRAINAGE

- PROPOSED SANITARY DRAINAGE

LINE TYPE LEGEND ROOF WATER

- PROPOSED STORMWATER DRAINAGE



SCALE 1:100 A3



CONTOUR

A.B.N. 62 117 061 659
PO Box 474, Buddina 4575, Qld
6 Innovation Parkway, Kawana Waters 4575, Qld
Ph. (07) 5493 9777 Fax (07) 5493 6888
Website: www.ContourCE.com.au



PLAN DETAILS:

Designed: **RM**
Drawn: **RM**
Checked: **BAT**
Datum: **AHD**
Date: **DEC 2021**

RPEQ 6068

PLAN AMENDMENTS:

Rev	Date	Comment	Altered	Checked
A	17/12/21	FOR APPROVAL	RM	JT

PROPOSED SHED REFURBISHMENT 48 SIPPY CREEK RD, TANAWAH SUNSHINE COAST REGIONAL COUNCIL

© This plan is Copyright. Other than for the purposes of and subject to the conditions prescribed under the Copyright Act, no part of it may in any form or by any means be reproduced, stored in a retrieval system or transmitted without the prior written permission of Contour Consulting Engineers. The plan shall not be used for construction without prior written approval.

PLAN TITLE:

**SANITARY DRAINAGE &
WATER RETICULATION FLOOR PLAN**

PLAN No: **1417 03 H 300**

REVISION: **A**

TENDER