

SPECIFICATION NOTES

GENERAL CONDITIONS

CONTRACTOR WORKS SHALL COMPLY WITH ALL RELEVANT PROJECT BRIEFS AND REQUIREMENTS. THE ELECTRICAL SERVICES DOCUMENTATION SHALL BE READ IN CONJUNCTION WITH ALL OTHER PROJECT AND CONTRACT DOCUMENTATION. CO-ORDINATE ALL CONTRACTORS' WORK WITH OTHER TRADES AND BUILDERS WORKS.

INSPECTION

THE CONTRACTOR SHALL FULLY INFORM THEMSELVES OF ALL ASPECTS OF THE EXISTING INSTALLATION PRIOR TO TENDER AND COMMENCEMENT OF CONSTRUCTION. MANDATORY SITE INSPECTIONS SHALL BE ADVISED BY THE PRINCIPAL. DISCRETIONARY VISITS SHALL BE ARRANGED BY THE CONTRACTOR IN CONJUNCTION WITH THE PRINCIPAL OR THEIR REPRESENTATIVE.

CODES, RULES, PERMITS, FEES

ALL MATERIALS, SUPPLIES, AND ALL WORK INSTALLED UNDER THE CONTRACT SHALL COMPLY WITH LATEST APPROVED VERSIONS (INCLUDING REFERENCED STANDARDS) OF THE CODES, STANDARDS, RULES AND REGULATIONS OF RELEVANT STATUTORY AUTHORITIES INCLUDING, BUT NOT LIMITED TO:

- A. BUILDING CODE OF AUSTRALIA
- B. ELECTRICAL SAFETY ACT
- C. WORKPLACE HEALTH & SAFETY ACT
- D. ELECTRICAL SUPPLY AUTHORITY REGULATIONS
- E. QLD ELECTRICITY CONNECTION MANUAL (QECM), AND QLD ELECTRICITY METERING MANUAL (QEMM)
- F. AS/NZS 3000 ELECTRICAL INSTALLATIONS (WIRING RULES)
- G. AS/NZS 61439 LOW-VOLTAGE SWITCHGEAR AND CONTROL GEAR
- H. AS/NZS 3008 ELECTRICAL INSTALLATIONS (SELECTION OF CABLES)
- I. AS/NZS 3017 ELECTRICAL INSTALLATIONS (VERIFICATION GUIDELINES)
- J. AS 60529 DEGREES OF PROTECTION PROVIDED BY ENCLOSURES (IP CODE)

OBTAIN A COPY OF RELEVANT STANDARDS FOR REFERENCE AS REQUIRED PRIOR TO COMMENCEMENT OF WORKS.

MAKE ALL APPLICATIONS AND PAY ALL FEES REQUIRED TO COMPLY WITH RELEVANT AUTHORITY REQUIREMENTS, INCLUDING SELF-CERTIFICATION COSTS FOR ELECTRICAL INSPECTION.

CONTRACTOR LICENSING

ALL ELECTRICAL WORKS SHALL BE UNDERTAKEN BY LICENSED ELECTRICAL CONTRACTOR/S. QUALIFIED AND EXPERIENCED IN THE TYPE OF WORK REQUIRED FOR THIS PROJECT. LICENSING AND QUALIFICATIONS SHALL COMPLY WITH THE REQUIREMENTS OF THE RELEVANT JURISDICTION WITHIN WHICH THE WORKS ARE BEING UNDERTAKEN.

WORKMANSHIP

ALL WORKMANSHIP AND MATERIALS SHALL BE PROVIDED TO THE SATISFACTION OF THE SUPERINTENDENT. ALL MATERIAL WILL BE NEW UNLESS OTHERWISE NOTED. ANY MATERIALS OR WORKMANSHIP WHICH ARE CONSIDERED INFERIOR OR NON-CONFORMING BY THE SUPERINTENDENT SHALL BE REPLACED AT THE CONTRACTOR'S COST.

DEFECTS LIABILITY

PROVIDE GUARANTEE/S FOR QUALITY AND WORKMANSHIP OF ALL WORK AND MATERIALS AGAINST DEFECTS, FOR A PERIOD OF TWELVE MONTHS FROM THE DATE OF ISSUE OF THE 'CERTIFICATE' OF PRACTICAL COMPLETION. DURING THIS PERIOD, PROMPTLY REPLACE ALL DEFECTIVE EQUIPMENT, FIXTURES AND MATERIALS AT NO ADDITIONAL COST. REFER CONTRACT CONDITIONS FOR FURTHER DETAIL REGARDING DEFECTS LIABILITY AND COMPLETION REQUIREMENTS.

EXISTING SERVICES

ACCURATELY LOCATE AND IDENTIFY ALL RELEVANT EXISTING SERVICES (IN-GROUND OR OTHERWISE) IN THE VICINITY OF THE WORKS AREA. LIAISE WITH ALL RELEVANT SERVICE AUTHORITIES AS REQUIRED. DAMAGE TO EXISTING SERVICES SHALL BE RECTIFIED AT THE CONTRACTORS' EXPENSE.

NEW SERVICES

THE LOCATION AND MOUNTING HEIGHTS OF THE SERVICES SHOWN ON THE DRAWINGS ARE APPROXIMATE ONLY. FINAL LOCATIONS, MOUNTING HEIGHTS AND CABLING PATHWAYS SHALL BE COORDINATED ON-SITE (WITH OTHER TRADE WORKS AND EXISTING BUILDING AND IN-GROUND ELEMENTS) FROM DIMENSIONED SETOUTS.

RELATED WORKS

COORDINATE AND COOPERATE WITH ALL OTHER TRADE DISCIPLINES. NOTE THE FOLLOWING SPECIFIC COORDINATION ELEMENTS:

- A. BUILDERS WORKS: ENSURE ALL TRADE WORKS ARE COORDINATED WITH ASSOCIATED BUILDERS WORKS.
- B. SPECIALIST EQUIPMENT: COORDINATE FINAL OUTLET RATINGS AND LOCATION WITH EQUIPMENT PROVIDERS/INSTALLERS.

OBTAIN A SET OF ARCHITECTURAL, STRUCTURAL, CIVIL AND OTHER SERVICES DOCUMENTATION (AS APPLICABLE) FOR REVIEW AND COORDINATION PRIOR TO COMMENCEMENT OF CONSTRUCTION.

SCOPE OF WORK

THE SCOPE OF WORK INCLUDES THE SUPPLY, DELIVERY, COORDINATION, INSTALLATION, TESTING AND COMMISSIONING AND DEFECTS LIABILITY SUPPORT OF THE SYSTEMS AND EQUIPMENT AS SHOWN ON THE DRAWINGS. SUPPLY ALL THE REQUIRED MATERIALS UNLESS OTHERWISE SPECIFIED. THE SCOPE OF WORK INCLUDES BUT IS NOT NECESSARILY LIMITED TO THE FOLLOWING:

DEMOLITION

- A. EXTENT OF WORKS: PRIOR TO TENDERING, OBTAIN A SET OF ARCHITECTURAL DEMOLITION DRAWINGS AND INSPECT THE SITE TO ASSESS THE EXTENT OF THE DEMOLITION WORK.
- B. GENERAL: COMMENCE DEMOLITION IN AN ORDERLY FASHION AS DIRECTED BY THE SUPERINTENDENT. DISCONNECT, REMOVE AND MAKE SAFE ALL ELECTRICAL EQUIPMENT AND CABLING MADE REDUNDANT BY THE NEW WORK.
- C. RETAINED SERVICES: KEEP ADJACENT CONNECTED SERVICES OPERATIONAL BY TEMPORARY CABLING AS NECESSARY, SO AS NOT TO INTERFERE WITH THE USE OF THE BUILDING BY OCCUPANTS. INVESTIGATE THE WIRING AS WORK PROCEEDS. ASCERTAIN THE ORIGIN OF THE SUPPLY AND WHERE THE CABLES TERMINATE. IF THE SERVICE IS NOT CLEARLY DOCUMENTED TO BE RETAINED OR DEMOLISHED, ONCE THE NATURE OF THE CIRCUIT HAS BEEN ASCERTAINED, ADVISE THE SUPERINTENDENT WHO WILL GIVE A DIRECTION AS TO WHETHER THE DEMOLITION IS TO PROCEED OR THE CABLE IS TO BE RETAINED UNDAMAGED.
- D. SHUTDOWNS: COORDINATE ALL REQUIRED ELECTRICAL SUPPLY ISOLATIONS WITH THE SUPERINTENDENT AND PRINCIPAL. NO SUPPLY ISOLATIONS SHALL BE UNDERTAKEN WITHOUT THE PRIOR WRITTEN APPROVAL OF THE SUPERINTENDENT AND/OR PRINCIPAL.

POWER SUPPLY AND DISTRIBUTION

- A. UTILITY SUPPLY: EXISTING TO REMAIN.
- B. MAIN SWITCHBOARD: EXISTING TO REMAIN
- C. DISTRIBUTION SWITCHBOARDS: PROVIDE DISTRIBUTION SWITCHBOARDS AS SPECIFIED. SWITCHBOARDS SHALL BE TYPE-TESTED (TO AS/NZS 3439 OR AS/NZS 61439), PROPRIETARY PANEL-BOARDS/LOAD CENTRES.
- D. METERING: EXISTING TO REMAIN
- E. SELECTIVITY: PROVIDE A FULLY GRADED SYSTEM COMPLYING WITH THE REQUIREMENTS OF AS/NZS 3000, INCLUDING COORDINATION WITH EXISTING UPSTREAM PROTECTION TO THE SUPPLY AUTHORITY POINT OF ENTRY. ENSURE ALL PROTECTION DEVICES ARE RATED SUCH THAT REQUIRED SELECTIVITY IS MAINTAINED THROUGHOUT THE DISTRIBUTION NETWORK.
- F. FAULT LEVEL: ENSURE EQUIPMENT AND PROTECTION DEVICES ARE RATED TO WITHSTAND THE PROSPECTIVE SHORT CIRCUIT CURRENT (FAULT CURRENT) AT EACH POINT IN THE NETWORK. THIS CAN BE ACHIEVED VIA SUITABLY RATED PROTECTION DEVICES OR ALTERNATIVELY THROUGH THE IMPLEMENTATION OF A CASCADED COMBINATION OF BREAKERS. IF A CASCADED SYSTEM IS PROPOSED, PROVIDE EVIDENCE FROM THE MANUFACTURER THAT THE PROPOSED COMBINATION OF DEVICES HAS BEEN TESTED FOR THIS APPLICATION. MINIMUM FAULT CURRENT RATING OF MCB'S SHALL BE 10kA.
- G. RCD PROTECTION: PROVIDE 30mA RCD PROTECTION TO ALL POWER (AND LIGHTING) CIRCUITS IN ACCORDANCE WITH AS/NZS 3000.
- H. GENERAL POWER: SUPPLY, INSTALL AND CONNECT ALL NEW POWER OUTLETS AND ACCESSORIES AS INDICATED. COORDINATE FINAL LOCATION AND RATING WITH SPECIALIST EQUIPMENT INSTALLERS WHERE RELEVANT.
- I. CIRCUITING: ADJUST THE CIRCUITING AS REFERENCED ON THE DRAWINGS AS REQUIRED TO COORDINATE WITH FINAL CABLING PATHWAYS AND SITE CONDITIONS. ENSURE OVERALL CIRCUIT LOADING DOES NOT EXCEED THE RATING OF THE CIRCUIT AND CABLING.
- J. LABELLING: ALL OUTLETS AND ACCESSORIES SHALL BE FITTED WITH DURABLE CIRCUIT IDENTIFICATION LABELS (INCLUDING UNDER REMOVABLE FACEPLATES WHERE APPLICABLE). LABELS SHALL ONLY BE REMOVABLE WITH THE USE OF A TOOL.
- K. CIRCUIT SCHEDULE/S: PROVIDE TYPED CIRCUIT SCHEDULES AT EACH SWITCHBOARD SUPPLIED UNDER THE WORKS. CIRCUIT SCHEDULES SHALL ALSO INCLUDE: ORIGIN OF SUPPLY, MAINS/SUBMAINS (UPSTREAM) PROTECTION DEVICE RATING, MAINS/SUBMAINS (UPSTREAM) CABLE TYPE/SIZE.

LIGHTING

- A. GENERAL: PROVIDE LIGHTING AS INDICATED ON THE DRAWINGS.
- B. LUMINAIRES: ALL LUMINAIRES SHALL CONFORM TO THE FOLLOWING:
 - SUPPLIED COMPLETE WITH ALL REQUIRED CONTROL GEAR AND MOUNTING ACCESSORIES TO SUIT THE INTENDED APPLICATION AND MOUNTING LOCATION. PROVIDE ADDITIONAL MOUNTING SUPPORTS AS REQUIRED IF MOUNTING LOCATION DIFFERS FROM MANUFACTURER RECOMMENDATIONS.
 - HAVE UNDERGONE NATA ACCREDITED TESTING AND HAVE LM-79, LM-80 AND TM-21 TEST REPORTS AVAILABLE.
 - REGISTERED WITH ELECTRICAL REGULATORY AUTHORITIES COUNCIL (ERAC) AND PROVIDED WITH REGULATORY COMPLIANCE MARK (RCM). THIS INCLUDES CONTROL GEAR.
 - INSTALLED TO MANUFACTURERS REQUIREMENTS, AND IN ACCORDANCE WITH RELEVANT STANDARDS/ REQUIREMENTS.
 - PROVIDED WITH SURGE PROTECTION.
 - PROVIDED WITH CAPPED 7-PIN NEMA SOCKET FOR FUTURE SMART CITY NODE (WIRED TO DALI DRIVER).
 - PROVIDED WITH DALI COMPLIANT DRIVER (WIRED TO CAPPED 7-PIN NEMA).
- C. IP RATING: WIRE ALL IP RATED LUMINAIRES TO MATCH THE IP RATING INDICATED AND INSTALLED TO MANUFACTURER REQUIREMENTS. PROVIDE ALL REQUIRED MOUNTING/CABLING ACCESSORIES, WHERE APPLICABLE, PROVIDE MOUNTING SUPPORT WITHIN PITS TO ENSURE IN-PIT CONTROL GEAR IS NOT LOCATED AT THE BASE OF THE PIT.
- D. IK RATING: INSTALL LUMINAIRE TO MANUFACTURE REQUIREMENTS TO ENSURE THE IK RATING IS MAINTAINED THROUGH THE LUMINAIRE FIXING METHODOLOGY.
- E. ALTERNATE SELECTIONS: ALTERNATE LIGHT FITTINGS WILL NOT BE ACCEPTED WITHOUT WRITTEN APPROVAL FROM SUPERINTENDENT OR THEIR REPRESENTATIVE. IF/WHEN PROPOSING ALTERNATIVES, PROVIDE ALL RELEVANT TECHNICAL DATA AND LIGHTING CALCULATIONS FOR REVIEW (IN ORDER FOR THE PRINCIPAL TO MAKE A DETERMINATION ON EQUALITY OF PERFORMANCE).

- F. RCD PROTECTION: PROVIDE 30mA RCD PROTECTION TO ALL LIGHTING (AND POWER) CIRCUITS IN ACCORDANCE WITH AS/NZS 3000.
- G. LIGHTING CONTROLS: LIGHTING CONTROL'S SHALL BE AS DETAILED ON THE DRAWINGS. WHERE A PROPRIETARY CONTROL SYSTEM IS DOCUMENTED, THE CONTRACTOR SHALL LIAISE WITH RELEVANT REPRESENTATIVE/S OF THE SYSTEM PROVIDER TO REFINE AND FINALISE PRODUCT/ACCESSORY DETAILS.

CABLING AND CABLE SUPPORT SYSTEMS

- A. GENERAL: ALL POWER AND LIGHTING CABLES SHALL BE THERMOPLASTIC INSULATED (T.P.I) AND SHEATHED (T.P.S) 0.6/1.0kV GRADE AS APPLICABLE WITH AS 5000.1. INSULATION SHALL BE V75 GRADE.
- B. MINIMUM ELECTRICAL CABLE SIZES: SHALL BE AS FOLLOWS:
 - SUBMAINS CABLING: TO AS/NZS 3008
 - LIGHTING SUB-CIRCUITS (INCLUDING EMERGENCY LIGHTING): 2.5mm²
 - GENERAL PURPOSE POWER CIRCUITS: 2.5mm²
 - POWER TO SPECIALIST EQUIPMENT: TO SUIT CIRCUIT RATING (AS CONFIRMED WITH EQUIPMENT INSTALLER)
 - CONTROL CIRCUITS: 2.5mm²
 - FLEXIBLE CORDS: 300.25mm²
- C. CATENARY WIRE: PROVIDE CATENARY SUPPORTS WHERE REQUIRED. CATENARY SHALL BE STAINLESS STEEL OR COATED GALVANIZED CABLE (INCLUDING COUPLINGS). FIX ALL CATENARY TO THE BUILDING STRUCTURE.
- D. CABLE PENETRATIONS: DO NOT PENETRATE STRUCTURAL MEMBERS WITHOUT PRIOR APPROVAL FROM THE PROJECT STRUCTURAL ENGINEER AND/OR BUILDER. PROVIDE SUITABLE MECHANICAL PROTECTION (EG. GLANDING) FOR PENETRATIONS THROUGH METALLIC FRAMING ELEMENTS.
- E. SEGREGATION: MAINTAIN REQUIRED SEGREGATION OF DIFFERENT CABLING SYSTEM CLASSES (NEW AND EXISTING) THROUGH THE ENTIRE LENGTH OF THE CABLE RUN. COORDINATE WITH OTHER CABLING SYSTEM INSTALLERS AS REQUIRED.
- F. INSTALLATION: ALL CABLING AND CABLE SUPPORT SYSTEMS SHALL BE CONCEALED IN CEILING SPACES AND/OR CAVITY WALLS UNLESS INDICATED OR APPROVED OTHERWISE. PROVIDE ADDITIONAL CABLE SUPPORT INFRASTRUCTURE AS REQUIRED (EVEN IF NOT SHOWN ON THE DRAWINGS) TO ENSURE THE CABLING INSTALLATION IS COMPLIANT AND NEAT/TIDY.

CONDUITS AND TRENCHING

- A. GENERAL: PROVIDE ALL CONDUITS AS SHOWN ON THE DRAWINGS AS WELL AS ANY OTHER CONDUITS REQUIRED TO ACHIEVE COMPLIANCE WITH THIS SPECIFICATION. CHECK CONDUIT ROUTES ON SITE FOR INTERFERENCE FROM EXISTING SERVICES AND FOR ACCURATE LENGTHS BEFORE ORDERING.
- B. DRAW WIRES: ALL CONDUITS PROVIDED SHALL BE PROVIDED WITH NYLON DRAW WIRES.
- C. MARKER TAPE: LAY AN APPROVED TYPE PVC MARKER TAPE COMPLIANT WITH AS/NZS 2648.1 AND INSTALLED FOR THE FULL LENGTH OF CONDUIT RUNS AS FOLLOWS:
 - GENERAL: DETECTABLE TYPE WITH INTEGRAL STAINLESS STEEL WIRE
 - ELECTRICAL: TO COMPLY WITH AS/NZS 3000
 - COMMUNICATIONS: TO COMPLY WITH AS/CA S009
- D. EXCAVATION WORKS: SHALL COMPLY WITH THE FOLLOWING:
 - ALL EXCAVATION WORKS SHALL COMPLY WITH RELEVANT TREE PROTECTION REQUIREMENTS. REFER GENERAL CONDITIONS AND/OR LANDSCAPE DOCUMENTATION FOR REQUIREMENTS.
 - CONFIRM ALL CONDUIT ROUTES ONSITE PRIOR TO COMMENCING EXCAVATION WORKS.
 - EXCAVATE TRENCHES SO THAT CONDUITS ARE NOT LESS THAN 500mm BELOW GROUND LEVEL.
 - TAKE CARE DURING EXCAVATION TO AVOID DAMAGE TO EXISTING UNDERGROUND INSTALLATIONS. ANY DAMAGE CAUSED SHALL BE MADE GOOD.
 - CLEAR THE BOTTOM OF ALL ROCKS, STONES AND OTHER HARD/SHARP MATERIALS AND FILL TO A DEPTH OF 50mm WITH A LAYER OF SELECTED FILLING IN THE BOTTOM OF THE TRENCH.
 - WHERE TRENCHES ARE LEFT OPEN DURING CONSTRUCTION WORKS ENSURE THAT THEY ARE PROTECTED BY BARRICADES OR IN SUCH A MANNER AS TO PREVENT THEM CREATING A HAZARD
 - UTILISE UNDER-BORING OR VACUUM EXCAVATION WHEN EXCAVATING IN AND AROUND ROOT ZONES.
- E. BACKFILL AND MAKE-GOOD: SHALL COMPLY WITH THE FOLLOWING:
 - BACKFILL THE TRENCH ONLY AFTER THE SUPERINTENDENT HAS APPROVED THE LAID CONDUITS.
 - MAKE GOOD EXISTING PAVING, KERBING AND LANDSCAPING TO THE SATISFACTION OF THE SUPERINTENDENT.
 - REMOVE ALL EXCESS EXCAVATED SPOIL.
- F. SURFACE MOUNTED CONDUIT: PROVIDE SURFACE MOUNTED CONDUIT WHERE INDICATED. SURFACE MOUNTED CONDUIT SHALL BE COORDINATED WITH THE STRUCTURE TO WHICH IT IS TO BE MOUNTED AND SHALL BE PROVIDED WITH ALL REQUIRED MOUNTING CLIPS (STAINLESS STEEL) AT SUITABLE CENTRES TO ENSURE CONDUIT AND CABLE ARE ADEQUATELY SUPPORTED.

EARTHING & BONDING

- A. PROTECTIVE EARTHING: ENSURE ALL PROTECTIVE EARTHING IS INSTALLED IN ACCORDANCE WITH AS/NZS 3000.
- B. EQUIPOTENTIAL BONDING: PROVIDE EQUIPOTENTIAL BONDING TO ALL RELEVANT CONDUCTIVE ELEMENTS IN ACCORDANCE WITH AS/NZS 3000, INCLUDING (BUT NOT LIMITED TO) CONDUCTIVE PIPING (EG. WATER, GAS, OTHER), CONDUCTIVE CABLE SUPPORTS (EG. CABLE TRAY), STRUCTURAL METAL WORK AND CONDUCTIVE BUILDING MATERIALS. DAMP AREAS, TELECOMMUNICATIONS EARTHING SYSTEMS, MINIMUM SIZE OF EQUIPOTENTIAL BONDING CONDUCTOR SHALL BE 4mm² (6mm² FOR TELECOMMUNICATIONS).
- C. TESTING: UNDERTAKE MANDATORY TESTING INCLUDING EARTH CONTINUITY, EFLI AND RCD TESTING TO VERIFY EARTHING SYSTEM COMPLIANCE.

TESTING AND COMMISSIONING

- A. GENERAL: CARRY OUT TESTING, OPERATING AND ADJUSTING THE SYSTEM AND EQUIPMENT, AND FOR FULLY INSTRUCTING THE SUPERINTENDENT OR THEIR REPRESENTATIVE IN THE OPERATION OF THE SYSTEM AND EQUIPMENT. PROVIDE FULL OPERATOR'S MANUAL.

- B. ELECTRICAL: CARRY OUT TESTING IN ACCORDANCE WITH AS/NZS 3000 CLAUSE 8.3 AND 8.33 MANDATORY TESTS 8.3.10 OPERATION OF RCD'S.
- C. LIGHTING: TEST THE OPERATION OF ALL LUMINAIRE INSTALLED, TOGETHER WITH THE ASSOCIATED CONTROL STRATEGY. DEMONSTRATE THE FUNCTIONALITY OF THE CONTROL SYSTEM TO THE PRINCIPAL. ADJUST PROGRAMMABLE PARAMETERS AS REQUIRED TO SUIT THE PRINCIPALS REQUIREMENTS.
- D. TEST REPORTS: SUBMIT TEST REPORTS. PROVIDE THE SUPERINTENDENT WITH ALL TEST RESULTS, BOUND, FOR REVIEW. THE CERTIFICATE OF PRACTICAL COMPLETION WILL ONLY BE SIGNED AFTER THE COMPLETE TEST REPORTS HAVE BEEN REVIEWED.

AS-BUILT DRAWINGS AND MAINTENANCE MANUALS

- A. AS-BUILT DRAWINGS: PROVIDE A FULL SET OF AS-BUILT DRAWINGS WITHIN 14 DAYS OF PRACTICAL COMPLETION. ENSURE DRAWINGS COMPREHENSIVELY REFLECT DETAILS OF ALL INSTALLED SYSTEMS AND COMPONENTS. PROVIDE DRAWINGS IN THE FOLLOWING FORMATS (ON DISK OR SIMILAR APPROVED MEDIA):
 - HARD COPY - TO BE INCLUDED IN THE O&M MANUALS
 - PRINTABLE DOCUMENT FORMAT (PDF)
 - AUTOCAD (LATEST VERSION)
- B. ADAC: PROVIDE AS CONSTRUCTED DATA IN ACCORDANCE WITH SCC ADAC DATA STANDARDS AND GUIDELINES. REFER SCC WEBSITE FOR FURTHER REQUIREMENTS:
<https://www.sunshinecoast.qld.gov.au/Development/Development-Tools-and-Guidelines/Infrastructure-Guidelines-and-Standards/As-Constructed-Data-Standards-and-Guidelines>
- C. WARRANTIES: ENSURE THAT THE PRINCIPAL IS NAMED AS THE WARANTEE FOR ALL MANUFACTURER/SUPPLIER WARRANTIES EXTENDING BEYOND THE COMPLETION OF THE DEFECTS LIABILITY PERIOD.
- D. OPERATING & MAINTENANCE MANUALS: INCLUDE THE FOLLOWING AS A MINIMUM:
 - NAME, ADDRESS AND TELEPHONE NUMBERS OF THE MANUFACTURER AND SUPPLIER OF ITEMS OF EQUIPMENT INSTALLED, TOGETHER WITH CATALOGUE LIST NUMBERS. ALSO INCLUDE SUCH DETAILS FOR ALL CONSULTANTS AND CONTRACTORS INVOLVED IN THE DESIGN AND CONSTRUCTION PHASES.
 - PRODUCT LITERATURE FOR THE SYSTEMS INSTALLED.
 - MANUFACTURERS' OPERATIONAL AND SAFETY LITERATURE, AS APPROPRIATE.
 - EMERGENCY MAINTENANCE PROCEDURES, INCLUDING TELEPHONE NUMBERS FOR EMERGENCY SERVICES AND AFTER HOURS CONTACTS FOR SUPPLIERS AND CONTRACTORS AND PROCEDURES FOR FAULT FINDING.
 - STATUTORY CERTIFICATES OF COMPLIANCE FOR ALL ELECTRICAL AND COMMUNICATIONS WORK, COPIES OF MANUFACTURERS' WARRANTIES, CERTIFICATES FROM AUTHORITIES AND UTILITIES, PRODUCT CERTIFICATION, COPIES OF TEST CERTIFICATES, ETC.
 - AS-BUILT DRAWINGS, SYSTEM SCHEMATICS, SHOP DRAWINGS ETC.
 - TESTING AND COMMISSIONING RECORDS.
 - TRAINING AND OTHER HANDOVER MATERIAL AS APPLICABLE.
- E. CERTIFICATION: PROVIDE FORM 16 CERTIFICATION AS PART OF HANDOVER MATERIAL. CERTIFY THAT THE INSTALLATION COMPLIES WITH THE APPROVED DESIGN AND RELEVANT STANDARDS (EG. AS/NZS 3000).

A1

2	12.01.22	TENDER ISSUE		C.L	C.L
1	01.12.21	PRELIMINARY ISSUE		C.L	C.L
Rv	DATE	REVISIONS		REC.	APPR.

SURVEYED	
DRAWN	B.GRANT
CHECKED	C.LITTLETON
REVIEWED	C.LITTLETON
COORDINATOR	C.LITTLETON

WEBB AUSTRALIA

CONSULTING ELECTRICAL ENGINEERS - MECHANICAL CONSULTANTS

LIGHTING CONSULTANTS - TECHNOLOGY CONSULTANTS - COMMUNICATIONS CONSULTANTS

COPYRIGHT © 2016 WEBB AUSTRALIA GROUP (AUST PTY LTD AND ITS SUBS). ALL RIGHTS RESERVED. THIS DRAWING MAY NOT BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS IN PART OR IN WHOLE WITHOUT THE WRITTEN PERMISSION OF WEBB AUSTRALIA GROUP (AUST PTY LTD). WEBB DRAWINGS ARE EXCLUSIVE AND SHALL BE READ IN CONJUNCTION WITH ALL CONTRACT DOCUMENTATION. UNLESS ANY AMBIGUITY, ERROR, OMISSION, DISCREPANCY, INCONSISTENCY OR OTHER FAULT APPEAR TO EXIST IN THE DOCUMENT, THE DRAWING IS TO BE TAKEN AS THE CONTRACT ADMINISTRATION DOCUMENT.

WEBB AUSTRALIA GROUP - ACN 010 733 561

CAPITAL ONE COMPLEX, SUITE 13A

9 CAPITAL PLACE BIRTINGA QLD 4571

TEL: 07 5438 9800

FACSIMILE: (07) 3870 4100

EMAIL: sunshinecoast@webbaustralia.com.au

Q403A



Sunshine Coast

COUNCIL

SIPPY DOWNS DEPOT SHED REFURBISHMENT

ELECTRICAL SERVICES

SPECIFICATION

Project Number:

Q403A

Sheet No. - Revision No.

E0022

FILE:G:\Q403A - SIPPY DOWNS DEPOT\01 WEBB\01 ELECTRICAL\E002.dwg DATE:12/Jun/2022 BY:bgran